

CR 183969



**AUTOMATED FLUID INTERFACE SYSTEM (AFIS)  
FINAL REPORT DOCUMENT**

Prepared for:

**National Aeronautics and Space Administration  
George C. Marshall Space Flight Center  
Marshall Space Flight Center, AL 35812**

**APRIL 1990**

**NAS8-37457**

(NASA-CP-163969) AUTOMATED FLUID INTERFACE  
SYSTEM (AFIS) Final Report (Fairchild  
Technical Support Center) 49 p CSCL 14a

NSI-11031

63/14 Unclas 0291072

## FOREWORD

NASA has identified the need to develop a facility to conduct the on-orbit transfer of fluids either Situ via the OMV or while attached to the STS or Space Station Freedom. In response to that need, Fairchild Space has developed the Automated Fluid Interface System (AFIS) flight concept and demonstration unit. This report describes the Fairchild design in response to the AFIS contract requirements, contract number NAS8-37457.

## TABLE OF CONTENTS

FOREWORD	ii
TABLE OF CONTENTS	iii
LIST OF FIGURES	iv
LIST OF TABLES	v
1.0 INTRODUCTION	1
1.1 BACKGROUND	1
1.2 SUMMARY DESCRIPTION	1
2.0 SYSTEM TRADE STUDIES	2
2.1 DESIGN DRIVERS	2
2.2 TRADE STUDIES	2
3.0 AFIS APPLICATIONS	7
4.0 SUBSYSTEM DESCRIPTION	9
4.1 FUNCTIONAL DESCRIPTION	9
4.2 MECHANICAL DESIGN	9
4.2.1 Interfaces	9
4.2.2 Structure	11
4.2.3 Latch Mechanism	11
4.2.3 Coupler Shelf Drive System	12
4.2.5 Cover Mechanism	15
4.2.6 Coupler "Floating" Mount	16
4.3 AFIS STRUCTURAL ANALYSIS	19
4.4 ELECTRICAL SYSTEM	22
4.5 WEIGHT BUDGETS	26
4.6 THERMAL ASSESSMENT	27
4.6.1 Thermal Configuration	27
4.6.2 Thermal Analysis	27
4.6.3 Results and Recommendations	28
4.7 SAFETY ASSESSMENT	31
4.7.1 Safety Requirements Matrix	31
4.7.2 System Hazards	31
4.7.3 Fluid Coupler/Electrical Connector Layout	31
5.0 DEMONSTRATION UNIT	34
5.1 DEMONSTRATION OBJECTIVE	34
5.2 DEMO MECHANICAL CONFIGURATION	34
5.2.1 Cover Mechanism	34
5.2.2 Latch Mechanism	34
5.2.3 Shelf Drive Mechanism	34
5.2.4 Structure	35
5.3 DEMO ELECTRICAL SYSTEM	35
APPENDIX A WEIGHTS-FULLY LADEN (THREE TABLES)	38
APPENDIX B WEIGHTS-CRYOGEN CONFIGURATION (TWO TABLES)	40
APPENDIX C WEIGHTS-FLUID CONFIGURATION (TWO TABLES)	42
APPENDIX D DEMO WEIGHTS	44

## LIST OF FIGURES

Figure 1-1 AFIS Configuration	1
Figure 2-1 AFIS Mission Requirements Summary	4
Figure 2-2 Outside clearance on OMV With TPDM Docking System	5
Figure 2-3 Outside clearance on OMV With RGDM Docking System	5
Figure 2-4 AFIS Multi-Case Option	5
Figure 2-5 Baseline AFIS Bi-Propellant Fluid Transfer Arrangement	6
Figure 2-6 Pros & Cons of Single Vs. Multiple Units	6
Figure 3-1 AFIS Resupplying Spacecraft With OSCRS and OMV	7
Figure 3-2 AFIS Resupplying Spacecraft Using RGDM	7
Figure 3-3 AFIS Resupplying OMV From OSCRS Using a TPDM	7
Figure 3-4 AFIS Inside the Shuttle Bay with OMV and OSCRS	8
Figure 3-5 TWO AFISs Supporting Space Station Operations	8
Figure 4-1 AFIS/RGDM Compatibility	9
Figure 4-2 AFIS/RGDM Compatibility	10
Figure 4-3 OMV 15° Alignment Requirement	10
Figure 4-4 AFIS Structural Inboard Profile	11
Figure 4-5 AFIS Latch Mechanism	12
Figure 4-6 AFIS Internal Mechanism	12
Figure 4-7 AFIS 1 Shelf Configuration	13
Figure 4-8 AFIS 2 Shelf Configuration	13
Figure 4-9 AFIS 3 Shelf Configuration	14
Figure 4-10 AFIS Emergency Disconnect	15
Figure 4-11 Cover Mechanism	15
Figure 4-12 Fluid Transfer Cover Arrangement	16
Figure 4-13 Cryo Transfer Cover Arrangement	16
Figure 4-14 Backup Mechanism Backup Release	17
Figure 4-15 Backup Mechanism Backup Release After Operation is Complete	17
Figure 4-16 AFIS Alternate Cover Configuration	18
Figure 4-17 Fluid and Cryogenic Coupler Floating Feature	18
Figure 4-18 Von Mises Stress Plot of AFIS Showing Results For Worst Case Liftoff/Landing Loads	20
Figure 4-19 Von Mises Stress Plot of AFIS Showing Results For Worst Case Fluid Transfer Loads	20
Figure 4-20 First Natural Frequency and Corresponding Mode Shape In Stowed Configuration	21
Figure 4-21 Latch Control and Telemetry Block Diagram	24
Figure 4-22 Cover Control and Telemetry Block Diagram	24
Figure 4-23 Shelf Control and Telemetry Block Diagram	25
Figure 4-24 Latch Bolt Pyro, Emergency Disconnect and Temperature Measurement	25
Figure 4-25 AFIS Mass Budget Summary	26
Figure 4-26 AFIS Thermal Configuration	29
Figure 4-27 AFIS Thermal Configuration	30
Figure 4-28 STS Payload Safety Requirements Applicability Matrix	32
Figure 4-29 AFIS Safety Assessment	32
Figure 4-30 Fluid Coupler and Electrical Connector Layout	33
Figure 5-1 AFIS/Controller Interconnect Diagram	37
Figure 5-2 AFIS Remote Controller	37

## LIST OF TABLES

Table 1. Electrical Interfaces	23
Table 2. Electrical Hardware	23
Table 3. AFIS Temperature Requirements	28
Table 4. AFIS Assumed Environmental Factors	28
Table 5. Thermal Analysis Results	29
Table 6. Worst Case Heater Power Requirements	29
Table 7. Demo Electrical Interfaces	36
Table 8. Demo Electrical Hardware	36

## 1.0 INTRODUCTION

### 1.1 BACKGROUND

Automated remote fluid servicing will be necessary for future space missions, as future satellites will be designed for on-orbit consumable replenishment. In order to develop an on-orbit remote servicing capability, a standard interface between a tanker and the receiving satellite is needed.

The objective of the Automated Fluid Interface System (AFIS) program is to design, fabricate, and functionally demonstrate compliance with all design requirements for an automated fluid interface system. This effort was done for the Marshall Space Flight Center, contract NAS8-37457.

This report provides a description and documentation of the Fairchild AFIS design. The Fairchild requirements are documented in the "AFIS Requirements Document", Fairchild, Nov 1989, NAS8-37457, and the test plan is documented in the "Test Plan and Operational Procedures", Fairchild, April 1989, NAS8-37457.


### 1.2 SUMMARY DESCRIPTION

The Automated Fluid Interface System (AFIS) is an automated system that provides the capability for remote satellite refueling. It is designed to be compatible with the space servicing infrastructure which includes the Space Transportation System (STS), the Space Station, the Orbital Spacecraft Consumables Resupply System (OSCRS), and the Orbital Maneuvering Vehicle (OMV).

AFIS is designed to be a flexible, completely redundant, reconfigurable system capable of resupplying either cryogenics or bi-propellants and monopropellants. It can accommodate up to 8 fluid type couplers, 4 gas couplers and 8 C&DH electrical connectors on a single mission. The

number and location of the coupler and connectors can be arranged as dictated by the mission requirements. It is designed to be compatible with the three Point Docking Mechanism (TPDM) and the Remote Grapple Docking Mechanism (RGDM) on the OMV and can be reused for 40 missions. The design meets all of the safety requirements of the STS. The AFIS is 5 feet in diameter and 17.5 inches high without the legs. The legs shown in **Figure 1-1** are 19 inches high in order to be compatible with the OMV, however, they could be shorter depending on the particular mission requirement. The total system, AFIS and legs, weighs between 325 to 450 pounds depending on the number of fluid couplers and electrical connectors required.

The AFIS can be left on orbit for an extended period of time since it does not require refurbishment between missions and contamination covers are provided to prevent debris from getting into the couplers and connectors.



**Figure 1-1 AFIS Configuration**

## 2.0 SYSTEM TRADE STUDIES

### 2.1 DESIGN DRIVERS

The principal design requirement of AFIS is to transfer cryogenics, propellants, liquids and high pressure gasses from one spacecraft to another. It is required to be compatible with Orbiting Maneuvering Vehicle (OMV) and OSCRS. Further, it must be compatible with the Three Point Docking Mechanism (TPDM) and the Remote Grapple Docking Mechanism (RGDM). One of the requirements of OMV is that a 15° docking clearance cone be provided. This requirement tends to drive the AFIS location toward the OMV centerline for maximum envelope usage and minimum connector travel.

AFIS is also required to provide redundancy. Providing redundant couplers and connectors consumes much of the available AFIS surface area. The number and sizes of the couplers and connectors for two AFIS configurations, including redundancy, is shown below:

#### Cryogen Transfer Configuration

- o 2 to 4 Cryogenic Couplers (6 inch Dia)
- o 4 to 8 Electrical Connectors (2 inch Dia)
- o 2 to 4 Gas Couplers (3 inch Dia)

#### Propellant Transfer Configuration

- o 4 to 8 Liquid Couplers (4 inch Dia)
- o 4 to 8 Electrical Connectors
- o 2 to 4 Gas Couplings

It is required that AFIS accommodate couplers/connectors as long as 15 inches on the AFIS side and 12 inches on the spacecraft side. This requirement drives the AFIS height.

The 2000 lbs pressure transfer force requirement is the design driver for the latch design. Other drivers include safety requirements and the need for contamination covers to keep

the couplers/connectors free of debris. One safety requirement is the need to keep the fuel and oxidizer at safe distances. **Figure 2-1** summarizes the AFIS design drivers. Further detail on these requirements is provided in the "AFIS Requirements Document", Fairchild Space, November 1989, NAS8-37457.

### 2.2 TRADE STUDIES

Two basic concepts were considered for AFIS. The baseline is the present configuration which houses all the couplers, connectors, latches, motors, etc in one unit. The second concept considered was a distributed system of two or more smaller units.

The baseline AFIS has approximately a 61 inch outer diameter and is 17.5 inches tall with legs 19 inches long. Since the baseline is one unit, it can straddle the TPDM with a 36 inch annular opening. The maximum distance from the spacecraft to the AFIS is 4 inches.

Since the alternate configuration is distributed into smaller units, it cannot straddle the TPDM and thus must be placed further away from the center of the OMV. **Figure 2-2** shows the maximum available space outside of the TPDM to be about 24 by 24 inches. This is a result of the 15° docking clearance cone and the TPDM diameter. This arrangement has a 16 inch distance to the spacecraft interface. **Figure 2-3** shows a similar arrangement with the OMV and the RGDM. A minimum of two distributed units are required if each have a diameter of 24 inches. Since the height of the RGDM is greater than the TPDM, the separation distance between the AFIS and the spacecraft would be 23 inches. This means that the AFIS would have to extend 23 inches in order for the fluid couplers and electrical connectors to mate with the spacecraft. This will

accommodate the worst case bipropellant configuration. The baseline AFIS's interfaces with the RGDM and TPDM are discussed in Section 4.2 Mechanical Design.

**Figure 2-4** shows a typical arrangement of one of the distributed units with the liquid couplers (4"Dia), Electrical connectors (2"Dia), and Gas couplers (3"Dia).

**Figure 2-5** shows the baseline AFIS configuration layout. With this

arrangement the MMH and NTO are kept 30 inches apart compared with 10 inches for the alternate configuration. Moreover, angular misalignment is reduced since the interface centerline is 48 inches compared with 70 inches for the alternate. **Figure 2-6** summarizes the pros and cons of the two options. The drawback of the single large unit baseline is the increased difficulty in ground handling because of its larger physical size.

• MISSION REQUIREMENTS

- Cryogenics, Bipropellants, Monopropellants, Water, Gas
- Maximum delivery pressure: 500 psi (Liquid), 6000 psi (Gas)

• DESIGN CONSTRAINTS

- Configuration: Attachment to OMV front face  
Compatibility with RGDM/TPDM  
Minimal contact w/ Spacecraft during docking (150 Misalignment)

- Mass, C.G.
- Construction

Materials/Processes: MSFC-STD-506, MSFC-SPEC-522  
MSFC-HDBK-527, MIL-STD-889B

Safety: NSTS 1700.7B,NHB 1700.1, NHB 8060.1B

Reliability (Provide redundancy to match OMV reliability)

Number and Size of Couplings/Connectors

Alignment Tolerances: Axial Overtravel of 0.25 inches  
Lateral Offset of +/- 0.10 inches  
Angular Misalignment of +/- 0.10

Lubrication: MSFC-STD-509 (Flight unit only)

Finish: MSFC-SPEC-250A (Flight Unit only)

Fastener Locking: MSFC-STD-561 (Flight unit only)

• MECHANICAL PERFORMANCE REQUIREMENTS

- STS versus ELV (Atlas, Delta II, Titan III)
- Ground Handling & Transportation Loads: FED-STD-101B, MIL-STD-810C  
(including Fabrication, Testing and Shock Loads)
- S/M Flight Loads: Quasi-static, Random Vibration, Acoustic  
Pressure, Shock, Crew-Applied Loads  
Fluid Transfer 2000 lbs total (may be all at one coupled)  
Mate/Demate: 10 lbs/gas coupling  
30 lbs/liquid coupling  
100 lbs/electrical connector
- Emergency Rapid Demate Loads (Water Hammer)  
(not applicable to prototype)
- Load path: Non-latching couplings  
AFIS operational loads must be borne by Mechanism
- Factors of Safety: MSFC-HDBK-505A
- Minimum Natural Frequency: 40 Hz (for mass > 50 lbs)
- S/M Analyses: Strength/Margins of Safety  
Rigidity/Minimum Natural Frequency  
Deflections  
Fatigue/Fracture Mechanics: MSFC-HDBK-1453

• THERMAL PERFORMANCE REQUIREMENTS

- Not applicable to Prototype Fabrication
- STS versus ELV versus Space Station
- Temperature Limits
- Orbital Flight Thermal Environment
  - Maximum solar radiation of 443.7 Btu/hr/sq. ft.
  - Maximum earth emitted radiation of 77 Btu/hr/sq. ft.
  - Space sink temperature of 3 degrees Kelvin
- Passive Design: Heaters, Isolators, MLI Blankets, Paints
- AFIS/OMV Isolation
- AFIS/Couplers Isolation

• OTHER NATURAL AND INDUCED ENVIRONMENTS

- NASA-TM-82473, NASA-TM-82478, NASA-TM-86460
- Meteoroid Impact
- Space Radiation

• ELECTRICAL PERFORMANCE REQUIREMENTS

- MSFC-SPEC-521
- OMV/AFIS Interface:
  - OMV front face electrical connector panel
  - TBD electrical connectors
  - Voltage range 22 VDC to 35 VDC
  - Power (5 KWHrs, 1 KW maximum)
  - Command data (256 words max, 1000 bps max)
  - Telemetry data (256 words max at OMV video data rate,  
serial data, discreet events, analog voltage)
- Mechanism Control Device
- Pyrotechnic/Ordinance Control Device: MIL-STD-1512
- AFIS/Spacecraft Interface:
  - 8 G&H Technology Connectors per GSFC Spec 700-42  
(882-700-002 Plug, 882-800-002 Receptacle)
  - Function?
- Safety:
  - three independent electrical inhibits
- Redundancy
  - Motors, Commutation devices electrically redundant
  - Limit switches redundant
- Electrostatic Discharge
- EMC

Figure 2-1 AFIS Mission Requirements Summary






Figure 2-5 Baseline AFIS Bi-Propellant Fluid Transfer Arrangement


	Multiple Small Units	Single Large Unit
Units Required	2-4	1
Diameter of Unit	17-23 inches	61 inches
Separation of Fuel & Oxidizer	10 inches	+30 inches
Weight	200-400 lbs	300-400 lbs
Redundancy	yes	yes
Distance From AFIS to SC	16-23 inches	4 inches
Attachment to OMV	8-12 places	4 places
Interface to OSCRS	Spread Out	Centralize
Alignment to SC	More Difficult	-
Integration	More Complex	-
Cable Runs	Long	Short
Propellant Lines Run	Long	Short
Flexible Reconfiguration	yes	yes
Controls Electronics	Multiple	Single
Handling	-	More Difficult

Figure 2-6 Pros & Cons of Single Vs. Multiple Units

### 3.0 AFIS APPLICATIONS


AFIS's compatibility with either OMV or OSCRS makes it suitable for a variety of freeflying spacecraft or manned based resupply operations. The resupply operation can be set up with either the RGDM or the TPDM in conjunction with OMV, OSCRS, Space Station, or the Space Shuttle.

The resupply of expendables to a spacecraft can either be done from OSCRS or from the OMV itself. **Figure 3-1** shows the AFIS resupplying a spacecraft from the OSCRS tanker. In this setup one RGDM is used to dock with the spacecraft and a second RGDM to fix the OSCRS to the OMV. By using OSCRS in unison with OMV, many spacecraft can be resupplied in one mission.




**Figure 3-1 AFIS Resupplying Spacecraft With OSCRS and OMV**

If only one spacecraft needs resupply, then the OMV itself can be used as a tanker. **Figure 3-2** shows the OMV docked to a spacecraft with AFIS providing the fluid, propellant, gas, and electrical interface. This interface works in both directions in the case that the OMV is itself being resupplied from a tanker. **Figure 3-3** shows the OMV being resupplied from OSCRS with a TPDM docking interface. In this type of operation the OSCRS could be attached to the Space Shuttle as shown in **Figure 3-4**.



**Figure 3-2 AFIS Resupplying Spacecraft Using RGDM**



**Figure 3-3 AFIS Resupplying OMV From OSCRS Using a TPDM**

**Figure 3-5** shows, AFIS can be incorporated into Space Station operations. This operation shows two AFIS units attached to an OSCRS and the two AFIS's attached to the Space Station and a spacecraft that could be an OMV. This arrangement allows resupply of the Space Station, or resupply of the freeflying spacecraft.




Figure 3-4 AFIS Inside the Shuttle Bay with OMV and OSCRS




Figure 3-5 TWO AFISs Supporting Space Station Operations

## 4.0 SUBSYSTEM DESCRIPTION

### 4.1 FUNCTIONAL DESCRIPTION

The operation of the AFIS can be accomplished remotely (i.e. from the ground, shuttle, or Space Station). Once the AFIS is docked with a satellite, the AFIS, upon command opens the contamination covers, raises and engages the latches, then raises the couplers and connectors up to mate with the coupler half on the spacecraft. The couplers automatically open when the two halves are mated. Another command opens the propellant valves (which are not part of AFIS) to allow transfer of the propellant. The AFIS latching mechanism is connected to prevent any of the propellant transfer loads to be induced into either the satellite or the tanker. The covers are closed after the system demates upon command.

### 4.2 MECHANICAL DESIGN

#### 4.2.1 Interfaces

The AFIS is currently planned to be used on the OMV as a mechanism to engage fluid couplers between the tanker and a receiving spacecraft. As such, the AFIS must be compatible with the docking mechanisms and the docking envelope of the OMV. The current design of the OMV has two docking mechanisms available for use, the RGDM (Remote Grapple Docking Mechanism) and the TPDM (Three Point Docking Mechanism). **Figure 4-1** shows the AFIS/RGDM compatibility. The AFIS was designed to fit inside the structural ring of the TPDM. The AFIS was designed to fit around the RGDM and not interfere with the camera and lights. The camera and lights can still be mounted in an allowable position on the TPDM with the AFIS mounted inside the docking ring. **Figure 4-2** shows how the AFIS fits when mounted with the TPDM. Additionally, the AFIS needed to avoid interfering with the 15° docking misalignment requirement of the OMV. **Figure 4-3** is an illustration

of the clearance available in a 15° misaligned position.




Figure 4-1 AFIS/RGDM Compatibility

The structural mounting of the AFIS to the OMV is accomplished by mounting the AFIS and a docking mechanism to the OMV through a common bolt. The AFIS has legs mounted to the structural housing of the mechanism which would extend to the bolt locations. This design was intended to minimize the impact in changing the docking mechanism design. At a future time and date, a study can be done to determine the feasibility of integrating the AFIS and the docking mechanism onto a single structure.

The interface between the AFIS and the serviced spacecraft is designed to accommodate some misalignment

between the spacecraft couplers and the AFIS couplers. As noted in the SOW for the AFIS design, the mechanism must be capable of functioning with a 0.1" lateral misalignment and a 0.25" axial misalignment. The lateral misalignment is accommodated at each individual coupler by a mechanism that allows the coupler to "float" within that envelope. The couplers on the serviced spacecraft are fixed to the interface plate and the couplers on the AFIS mechanism are allowed to "float." The axial misalignment requirement is met by designing the AFIS so that the couplers can extend the additional distance required to mate with the spacecraft.

One additional design requirement imposed on the AFIS was that "all fluid transfer loads must be borne by the interface mechanism." To accomplish this, a load path must be established between the AFIS and the spacecraft interface and a load path must be removed from between either the AFIS and the OMV or the spacecraft interface and the serviced spacecraft. The AFIS design accomplishes this by decoupling the spacecraft interface and allowing it to translate within a limited envelope and installing a latch mechanism. Given the latch mechanism, a load path is directly established between the AFIS and the spacecraft interface. Since the spacecraft interface is decoupled from the spacecraft, no load path exists between the AFIS and the spacecraft or the OMV for fluid transfer loads. Even if the load path requirement didn't exist, the latch mechanism would still be required for the AFIS. The RGDM is only capable of handling a 750 pound axial load and the AFIS design requirements states that the design load for fluid transfer is 2000 pounds.




Figure 4-2 AFIS/RGDM Compatibility





Figure 4-3 OMV 15' Alignment Requirement

### 4.2.2 Structure

The AFIS is a rigid toroidal structure that is supported by four legs. The main structure consists of a one piece machined base, to which six radial ribs are attached. The ribs are tied together at the top of the toroid by two machined rings. A sheet metal skin is attached to the base ring, ribs, and top rings on the inside and outside diameters of the toroid. For the flight unit, the ribs and the support legs would be made of aluminum honeycomb to minimize weight. All other machined structural components and the skins would be made of aluminum. The structure is designed to be riveted and bolted in order to allow for easy maintenance and reconfiguring. **Figure 4-4** is an illustration of some of the internal structural details of the AFIS.



**Figure 4-4** AFIS Structural Inboard Profile

### 4.2.3 Latch Mechanism

The Latch Mechanism is designed to serve as the structural load path between the AFIS and the spacecraft interface. As such, it must be capable of handling the 2000 pound fluid transfer load. Additionally, the Latch Mechanism must be capable of functioning given lateral misalignments. The basic principle of the latch is based on the MMS spacecraft module nut and acme screw. The spacecraft interface has three acme nuts attached to it. These nuts have a "floating" mechanism, similar to the fluid couplers. The AFIS has three acme screws which extend to engage the nuts on the spacecraft interface.

The latch screws are extended by rotating them through an acme nut attached to the AFIS. The operation of the latch screws is synchronized through the use of a chain and sprocket system. A hexagonal bushing is attached at the base of each latch screw. A hexagonal rod fits inside of the bushing. The rotation of this rod turns the acme screw and extends the latch screw toward the latch nut on the spacecraft interface. The sprockets are attached to the hexagonal rods and provide for the synchronization of the latch screws. The drive motor for the Latch Mechanism is attached to one of the latch screw drive sprockets. **Figure 4-5** is a section view of one Latch Mechanism engaged with the spacecraft to be serviced.




Figure 4-5 AFIS Latch Mechanism

and the latch screw on the AFIS unit are designed to separate from the AFIS when a pyro device is fired. This allows the tanker and the serviced spacecraft to separate after the refueling operation is complete in the event of a failure.

#### 4.2.3 Coupler Shelf Drive System

The Coupler Shelf Drive Mechanism performs the mating and demating of the connectors for the refueling mission. The system consists of a chain drive that synchronously operates some ball screws that raise a shelf. Attached to the shelf is a spacer and the individual fluid couplers. This mechanism is also capable of an emergency demate of all of the couplers. The design is intended to be reconfigurable in any generic form. The choice of coupler location is left to the user of the AFIS. Figure 4-6 illustrates the main components of the Coupler Shelf Drive Mechanism.

The chain drive system for the Latch Mechanism provides for a chain tension adjustment in order to prevent any slippage in the chain-sprocket interface. The chain tensioning system has two types of chain tensioners. The first is spring loaded tensioner that provides some compliance in the system to allow for any situations where slack may develop. It also maintains sprocket-chain contact if the chain tension should increase. The second type are screw adjustable tensioners used to set the nominal tension of the system.

The Latch Mechanism is designed to demate if the mechanism fails after engaging to the spacecraft interface. The acme nut




Figure 4-6 AFIS Internal Mechanism

The drive system is driven by a single motor that rotates the main drive sprocket. The chain in turn rotate the driven sprockets that are attached to the ball screws. As the ball screws rotate, the ball nuts that are attached to the shelves move up or down, depending on the direction of rotation. Each shelf has three ball screws attached to it. The spacer that is attached to the shelf is used to extend the couplers through the space between the AFIS and the spacecraft interface to the mating position.




Figure 4-7 AFIS 1 Shelf Configuration

The Coupler Shelf Drive System is designed to be reconfigurable. The drive motor can operate one to three shelves. This capability allows the user to optimize the AFIS to suit his requirements and reduce the weight of the mechanism if the entire mechanism is not necessary. **Figures 4-7, -8, and -9** are illustrations of typical one, two, and three shelf chain drive configurations, respectively, for the AFIS. The AFIS can carry the full complement of six shelves, either fully populated with couplers or a combination thereof. The AFIS has two separate drive systems to allow for redundancy. This enables the AFIS to accomplish its refueling mission if the primary drive system fails. This design imposes no penalties to the serviced spacecraft, as the AFIS design requirements dictate that the AFIS and the serviced spacecraft must have redundant couplers.




Figure 4-8 AFIS 2 Shelf Configuration




Figure 4-9 AFIS 3 Shelf Configuration

If an emergency situation arises during the refueling operation, then the couplers will need to be demated as quickly as possible to prevent damage to either spacecraft. Each Coupler Shelf Drive System has an emergency demate capability. The Emergency Demate Mechanism requires two components to operate. First, some stored energy must be available to move the shelves down and demate the couplers. Next, this stored energy must be released.

Stored energy is provided by three springs that compress when the coupler shelves reach their end of travel. This stored energy is maintained by preventing the ball screws from being backdriven and lowering the shelves. This is accomplished through the backdriving resistance of the drive motor. If the backdriving resistance of the motor is removed, then the spring energy is released, moving the shelves down and demating the couplers.

The backdriving resistance of the motor is removed through a shaft coupling that connects the motor to the main

drive sprocket. The main drive sprocket is attached to a coupling that has a tab which fits into a movable coupling. The movable coupling is attached to the output shaft of the drive motor. The movable coupling has springs installed to maintain engagement to the drive sprocket coupling. If an emergency arises, then a solenoid would be triggered to operate a lever and separate the two coupler halves. This would remove the backdriving resistance of the motor and the stored energy would be released to demate the fluid couplers. **Figure**

**4-10** is a section view of the emergency disconnect drive motor coupler. It is shown as a split view, to illustrate the engaged and disengaged positions.

A unique feature of the Emergency Demate Mechanism is that the fluid couplers can be mated again if the emergency is corrected. This would require triggering the solenoid to release the lever and allowing the shaft couplings to mate. Then the Coupler Shelf Drive Motor can be used to move the shelves up and mate the fluid couplers again and complete the servicing mission.

The Coupler Shelf Drive System also has a chain tensioning system that is similar to the Latch Mechanism. This system is intended to prevent any chain slippage during the emergency demate. This system will be installed and operational regardless of the shelf configuration.

### 4.2.5 Cover Mechanism

The baseline AFIS Cover Mechanism consists of two rings that are driven in separate tracks. Attached to each ring are two *fan* shaped covers, set on opposite sides of the ring. The rings rotate from an active section of the AFIS to an unused section. The cover rings are driven at a 2:1 ratio so that four sections of the AFIS are exposed when the covers are opened leaving two sections covered. The baseline mission types only require a two shelf arrangement for each Coupler Shelf Drive System. See Figure 4-11 for an illustration of the cover mechanism.

The cover rings are driven by a single motor that has a gearbox to provide two output sprockets. The output sprockets engage a chain that is imbedded in the cover rings. The output speeds of the sprockets are set at a 2:1 ratio so that the cover rings move at different speeds. The Upper Cover rotates 120° while the Lower Cover rotates 60°. This allows the two covers to rotate from adjacent sections of the AFIS and overlap over an unused section of the AFIS.

The covers are reconfigurable to allow for any combination of one or two shelves to operate. This is enabled by removing the *fans* from the cover rings and bolting the *fans* to a new location on the cover rings. Figures 4-12 and -13 show the two baseline cover configurations for a fluid and cryogenic transfer mission, respectively.

If the Cover Drive Motor should fail, then a backup mechanism can be operated to open the covers. First a pyro device would be fired to release the




Figure 4-10 AFIS Emergency Disconnect





Figure 4-11 Cover Mechanism

cover motor. A spring would rotate the motor away from the cover rings and disengage the drive sprockets from the embedded chain. A negator spring would then provide the necessary force to move the cover *fans* to the open position. Figures 4-14 and -15 show the working parts of the cover release mechanism before and after operating

the release mechanism, respectively. The servicing mission can then be accomplished without any difficulties.

The nominal position of the coupler is maintained through the use of two springs, one to hold the axial position and one to hold the lateral position. The housing for each coupler is designed to hold the coupler within the envelope specified by the angular and lateral misalignment. **Figure 4-17** illustrates a typical coupler floating mount.




**Figure 4-12 Fluid Transfer Cover Arrangement**


If all three shelves are required for a servicing mission, then an alternate cover mechanism can be installed. This mechanism consists of two lids that cover half of the AFIS and would rotate outward to expose all three shelves for operation. **Figure 4-16** illustrates the alternate covers in the open position. These covers would not interfere with the docking mechanisms or cameras. However, the covers would need to be stiff, due to the size of the lid. For this type of cover, the covers would need to be open prior to docking of the spacecraft and the OMV.

#### 4.2.6 Coupler "Floating" Mount


Each of the couplers and connectors that is mounted in the AFIS is mounted in a "floating" mechanism to accommodate the lateral and angular misalignment requirements of the AFIS.



**Figure 4-13 Cryo Transfer Cover Arrangement**



**Figure 4-14 Backup Mechanism Backup Release**



**Figure 4-15 Backup Mechanism Backup Release After Operation is Complete**




Figure 4-16 AFIS Alternate Cover Configuration




Figure 4-17 Fluid and Cryogenic Coupler Floating Feature

### 4.3 AFIS STRUCTURAL ANALYSIS

The AFIS structural analysis was performed on the AFIS system as a whole and on stress critical detailed structural components.

The AFIS system level structural analysis comprised a static analysis of the gravity loads induced during the launch and landing phases of the AFIS mission, and a static analysis of the fluid transfer loads. The gravity loads were studied for both the STS and the Titan, Atlas, and Delta ELV's. An eigenvalue analysis was done to determine the first natural frequency of the AFIS Mechanism. The safety factors used for all analyses were 1.25 for yield strength and 2.0 for ultimate strength.

The worst case gravity loads occurred during the STS launch and emergency landing cases. The gravity loads were based on the STS documentation and included an equivalent random input on one axis as specified in the MSFC stress analysis document. All possible load combinations were run with the worst case being X=-10.1 g, Y=-18.36 g, Z=-4.0 g. The analysis shows a maximum stress of 14,366 PSI, giving a margin of safety of 0.95 on yield strength and 0.46 on ultimate strength. **Figure 4-18** is a stress contour plot of the worst case liftoff/landing loads.

The operational loads of the AFIS unit were determined through the use of a detailed model of the ball screws, coupler shelf, and the spacer. Static forces were applied to this detail model to simulate the mating forces (including the emergency disconnect springs) and the fluid transfer forces. The reaction forces at the ends of the ball screws were then applied to the structure. The mating forces for the couplers/connectors were based on the AFIS SOW and are as follows:

100 lbs. per electrical connector  
(per GSFC-700-42)  
30 lbs. per fluid coupler  
10 lbs. per gas coupler

The fluid transfer load was 2000 lbs., in accordance with the SOW. This load was applied at a single coupler station. The fluid transfer load case was analyzed at every fluid coupler station, and the highest stress was 4,938 PSI. This stress gives a margin of safety of 4.67 for yield strength and 3.25 on ultimate strength. **Figure 4-19** is a stress contour plot of the worst case operational loads of the AFIS.

The eigenvalue analysis indicates that the first natural frequency of the AFIS occurs at 54.6 Hz. This exceeds the minimum requirement of 40 Hz for the AFIS system. **Figure 4-20** shows the mode shape of the AFIS mechanism at its first natural frequency.

The detail structural analysis was focused on the operational parts of the AFIS. Each of the Coupler Floating Mechanisms was analyzed for the coupler engagement and fluid transfer forces. The highest stress was 10,804 PSI, giving margins of 1.96 for yield strength and 1.08 on ultimate strength. The ball screws, coupler shelves, and spacers were analyzed as an assembly to study the engagement and fluid transfer loads. The highest stress was 8,554 PSI, giving margins of 2.74 for yield strength and 1.63 on ultimate strength.

In summation, the AFIS design is capable of handling all of the operational and environmental loads imposed upon it.




Figure 4-18 Von Mises Stress Plot of AFIS Showing Results For Worst Case Liftoff/Landing Loads





Figure 4-19 Von Mises Stress Plot of AFIS Showing Results For Worst Case Fluid Transfer Loads

ORIGINAL PAGE IS  
 OF POOR QUALITY



MODE: 1  
FREQ: 59.82 Hz

Figure 4-20 First Natural Frequency and Corresponding Mode Shape In Stowed Configuration

ORIGINAL PAGE IS  
OF POOR QUALITY

## 4.4 ELECTRICAL SYSTEM

The AFIS flight unit incorporates the required electrical design to interface remotely with and be compatible with the power, command and telemetry systems presently proposed for the NASA OMV, STS, or Space Station. Tables 1 and 2 list the electrical interfaces and hardware considerations for the AFIS flight unit.

There are three motor control systems on the AFIS: Latch, Cover, and Shelf control systems. These three systems along with the emergency demate and temperature measurement are routed through the Remote Interface Unit (RIU). The RIU is supplied by NASA and is compatible with the OMV's 1553 type bus. In effect, the AFIS RIU will look like another payload to the OMV. While the contract required one RIU, a second unit is recommended to provide for redundancy of the AFIS electrical control and telemetry systems.

The three AFIS motor control systems are similar. A schematic for each system is shown in **Figures 4-21, -22, and -23**. These systems take advantage of the multiplexing data bus provided by the OMV to drive the command decoder and telemetry multiplexer within the RIU to actuate and control the mechanisms and monitor the status.

The OMV will either issue a command or a status request to the RIU command decoder and the telemetry multiplexer responds with a reply. A typical sequence begins with the engage selection command of the latch then the latch on command is issued. Next, the priority select is tested. This command tests the decision logic, for instance in

the case of the shelf drive, a decision logic test prior to driving the shelf motor would be "are the covers open?".

Each of the three motor control systems is equipped with a position end of travel limit switch as the primary method for stopping the motor. A motor timer is provided as a "time-out" backup to the limit switch.

The emergency disconnect and latch bolt pyro systems shown in **Figure 4-24** are two independent operating systems used under different scenarios. The latch bolt pyro is only used as a last resort in separating the AFIS from the spacecraft. This system is implemented in the event that the AFIS latches cannot be retracted from the spacecraft. As such, the bolt pyros are enabled, armed, and fired. Thus, cutting the AFIS acme screw bolts which results in the acme screws remaining with the spacecraft. On the other hand, the emergency disconnect system can be actuated repeatedly with no system degradation to the AFIS or the spacecraft. If for instance, the mating of the AFIS couplers/connectors was not successful, the emergency disconnect is enabled, thus removing the motor/gearbox resistances from the ball screws holding up the platform. Once this resistance is removed the emergency demate springs are free to move the platform down approximately 3/4 of an inch. This movement demates all couplers and/or connectors which are mated.

**Figure 2-24** also shows the interface of the four thermistors to the telemetry multiplexer. These values are obtained when the OMV sends a status request.

**Table 1. Electrical Interfaces**

Power	Commands	Telemetry
Coupler Shelf Drive Motor	Latch Operation	Heater Thermistor Readout
Cover Mechanism Motor	Cover Mechanism Operation	Cover Status
Heater Power	Coupler Shelf Mechanism	Coupler Shelf Status
Latch Motor	Latch Pyro Operation	Latch Status
Latch Pyro	Emergency Disconnect Operation	Emergency Disconnect Status
		Latch Pyro Status

**Table 2. Electrical Hardware**

Name	Type
Coupler Shelf Drive Motor	Space Qualified Stepper Motor or Brushless DC Motor
Cover Mechanism Drive Motor	Space Qualified Stepper Motor or Brushless DC Motor
Latch Motor	Space Qualified Stepper Motor or Brushless DC Motor
Emergency Disconnect Solenoid	TBD
Heaters	TBD
Thermistors	TBD
Control Logic and Electronics	TBD
Latch Pyro Bolt Cutter	TBD

QUALITY  
 CONTROL




Figure 4-21 Latch Control and Telemetry Block Diagram




Figure 4-22 Cover Control and Telemetry Block Diagram

ORIGINAL PAGE IS  
OF FOUR QUALITY




Figure 4-23 Shelf Control and Telemetry Block Diagram




Figure 4-24 Latch Bolt Pyro, Emergency Disconnect and Temperature Measurement

## 4.5 WEIGHT BUDGETS

A mass budget was developed for each of the four flight configurations of the AFIS. The four configurations are as follows:

- A. Fully laden version with three spacer assembly tables
- B. Cryogen configuration with two tables
- C. Fluid configuration with two tables
- D. Demonstration

Figure 4-25 shows a weight summary for each of the four options.

A detailed breakdown of each entry in Figure 4-25 can be found in Appendices A through D. For example, the fully laden version (three table configuration) is detailed in Appendix A, the cryogen configuration is detailed in Appendix B, and so on. The drawing numbers of the components is shown in the comments column of each spreadsheet in the Appendices.

Each entry in Figure 4-25 comprises both the predicted weight and an associated weight margin. The weight margins correspond to the confidence in each component. A 20% margin is assigned to any part that is estimated. A 10% margin is assigned to any part where the weight is calculated, and a 5% margin is assigned to existing parts. The total margin of each configuration is a weighted average of the individual component margins. For instance, the total AFIS weight of the fully laden (three table) configuration has 54.37 lbs of margin, or a 13.28% margin of the quantity weight as shown in Appendix A

	THREE TABLES	(CRYO) TWO TABLES	(FLUID) TWO TABLES	SINGLE TABLE
MAIN STRUCTURE ASSY.-7A1200	195	176	176	157
FLUID SPACER ASSY.-7A1210	25	N/A	25	N/A
GAS/VELEC SPACER ASSY.-7A1220	25	25	25	25
CRYRO SPACER ASSY.-7A1230	24	24	N/A	N/A
TENSIONER ASSY.-7A1240	3	3	3	3
COVER MECHANISM ASSY.-7A1300	19	19	19	19
COVER GEAR HOUSING ASSY.-7A1301	2	2	2	2
DISCONNECT ASSY.-7A1400	4	4	4	4
LATCH MECHANISM-7A1500	19	19	19	19
THERMAL CONTROL HARDWARE	21	21	21	21
ELECTRONICS AND WIRING HARNESS	49	49	49	49
<i>AFIS Subtotal</i>	<i>386</i>	<i>342</i>	<i>343</i>	<i>299</i>
GFE COUPLERS AND CONNECTORS	79	60	60	25
<i>AFIS Total Weight and Margin</i>	<i>465</i>	<i>402</i>	<i>403</i>	<i>324</i>

Figure 4-25 AFIS Mass Budget Summary

The difference in weights between the four configurations occurs in the main structure, the number of tables (spacer assemblies), and the combination of couplers and connectors.

Listed below are six components within the main structure that have different quantities for the different configurations.

- A. Ball Screws.
- B. Thrust Bearing.
- C. Drive Sprockets.
- D. Idler Sprockets.
- E. Idler Shafts.
- F. Ball Screw Mtg Block

The quantity of these components for the single table configuration is typically a third as much as the three table option.

Each of the three types of spacer assemblies (tables) weigh approximately the same as shown in Figure 4-25.

The combination of couplers and connectors is dictated by the configuration requirements. The cryogen configuration, for example, has four cryogen couplers, four gas couplers, zero liquid couplers and eight electric connectors, as detailed in Appendix B.

#### 4.6 THERMAL ASSESSMENT

An initial thermal design and performance assessment was performed for the AFIS. While the AFIS might be utilized in a variety of orbital applications and in combination with different carrier vehicles, the thermal assessment study focuses on a single generic thermal design which could subsequently be optimized for a given mission. In this study, extreme environments and steady-state solutions were combined to yield very conservative analytical results.

The basic requirements to be met by the AFIS thermal design are derived from vendor information and previous hardware studies, such as OSCRS and OMV, and are given in Table 3. The most restrictive temperature range will apply to fluid subsystem components containing monopropellant and bipropellant fluids, such as MMH, NTO and  $N_2H_4$ . In addition to maintaining an adequate thermal environment for propellants and the AFIS equipment components, other goals of the thermal design are to minimize temperature gradients within the AFIS structure and to minimize heater power requirements.

##### 4.6.1 Thermal Configuration

The AFIS is conductively isolated from the carrier vehicle at the interfaces between the Base Ring and Strut Assemblies. Each electrical connector or fluid coupling is conductively isolated from the AFIS structure at its mounting flange.

Thermal isolators of 0.5 inch G-10 are used.

The AFIS is insulated from the radiation environment by the use of Multi-Layer Insulation (MLI) on all external surfaces and other surfaces with a view of space. Beta cloth comprises the outer layer. Ten-layer MLI is used on the contamination covers with twenty-layer MLI in all other locations. The Base Ring is closed out with MLI and therefore has no view of space or of the carrier vehicle. The Strut Assemblies and fluid and electrical lines between the AFIS and the carrier vehicle are enclosed with MLI and also have no view of space. This tends to isothermalize those components, promoting better alignment and thermal control.

Flight heaters are located near critical components, such as drive motors, electronics, and fluid subsystem hardware. The features of the initial thermal design for the AFIS are shown in Figures 4-26 and 4-27. It is assumed that the AFIS contamination covers are open and that there is no internal power dissipation other than that required for thermal control.

##### 4.6.2 Thermal Analysis

Steady-state solutions were obtained with a 15-node SINDA finite-difference model. Three cases were identified for analysis: the hot case, the propellant cold case, and the cryogen cold case. The assumed conditions for these cases are quite extreme and are noted in Table 4. In the hot case, the AFIS receives a full solar input from the forward direction and on all lateral external surfaces. In the cold cases, the AFIS receives no radiative input while viewing only space.

Certain assumptions have been made in order to perform this initial thermal assessment. These are related to MLI performance and expected environments. External environments were taken from the AFIS

Requirements Document. Carrier vehicle mounting surface temperatures were taken from OMV thermal analyses. The assumed properties are quite conservative in general and are given in Table 4.

#### 4.6.3 Results and Recommendations

Results from the AFIS thermal assessment are shown in Table 5.; estimated heater power requirements for both the propellant servicing and cryogen servicing missions are given in Table 6. These results are very conservative, being based on extreme environmental conditions and derived by steady-state solution, demonstrating that the AFIS thermal design as proposed herein should meet all basic thermal requirements. The thermal design may be optimized for particular missions to provide increased performance.

The AFIS should be operated at temperatures somewhat colder for the cryogen servicing case than for the propellant servicing case in order to minimize cryogen losses. The cryogen transfer losses are incurred only during the period of cryogen fluid transfer. Propellant cold case power requirements may be reduced by operating at cryogen case temperature levels before propellant fluid transfer, but thermal pre-conditioning of the AFIS will be required before any propellant transfer may take place.

**Table 3. AFIS Temperature Requirements**

PROPELLANTS	50°F to 120°F
DRIVE MOTORS	-100°F to 250°F
ELECTRICAL CONNECTORS	-55°F to 250°F
BALL SCREWS	-60°F to 250°F

**Table 4. AFIS Assumed Environmental Factors**

SOLAR CONSTANT	443.7 Btu/hr-ft <sup>2</sup>
SPACE SINK TEMPERATURE	3K (-455°F)
HOT CASE	FULL SUN FROM ALL DIRECTIONS MOUNTING SURFACE AT 25°F
PROPELLANT COLD CASE	NO RADIATIVE INPUTS MOUNTING SURFACE AT -15°F
CRYOGEN COLD CASE	NO RADIATIVE INPUTS MOUNTING SURFACE AT -15°F
MLI	10-LAYER EFFECTIVE EMISSIVITY = 0.05 20-LAYER EFFECTIVE EMISSIVITY = 0.03


**Table 5. Thermal Analysis Results**

	HOT CASE	PROPELLANT COLD CASE	CRYOGEN COLD CASE
RADIATIVE INPUTS	FULL SUN	NONE	NONE
MOUNTING SURFACE TEMPERATURE	25°F	-15°F	-15°F
CONNECTOR FRAME TEMPERATURE	40°C (104°F)	10°C (50°F)	-38°C (-38°F)
ENVIRONMENTAL LOSS MAKEUP	-	30W	10W
CRYOGEN TRANSFER LOSS MAKEUP	-	-	20W *

**Table 6. Worst Case Heater Power Requirements**

	PROPELLANT CASE	CRYOGEN CASE
COLD CASE ENVIRONMENTAL LOSSES	30W	10W
CRYOGEN TRANSFER LOSSES	-	20W*
CONTINGENCY	10W	10W
TOTAL AVERAGE POWE	40W	40W
PEAK POWER AT 50% DUTY CYCLE	80W	80W

\* REQUIRED DURING CRYOGEN TRANSFER ONLY.



**Figure 4-26 AFIS Thermal Configuration**

ORIGINAL PAGE IS  
OF POOR QUALITY




Figure 4-27 AFIS Thermal Configuration

## 4.7 SAFETY ASSESSMENT

### 4.7.1 Safety Requirements Matrix

A preliminary safety assessment has been performed for the AFIS system hardware and its operational aspects. Each element of the AFIS has been reviewed to establish how it relates to the specific requirements as defined in NHB 1700.7B. The review has made known those payload elements for which a hazard has been identified and for which a hazard must be controlled during the design, testing, and operation of the AFIS.

The AFIS Safety Requirements Matrix, shown in **Figure 4-28**, provides the relationship between individual AFIS subsystems and the requirements of specific sections of NSTS 1700.7B.

### 4.7.2 System Hazards

The hazards associated with the design and operation of the AFIS will be controlled by appropriate design, manufacturing, and operational measures taken to insure compliance with the requirements of NSTS 1700.7B and NHB 1700. **Figure 4-29** lists the major AFIS system hazards and indicates the type of activity or function which will be employed to control those hazards.

The AFIS structural elements and pressurized fluid components are made failure-tolerant by compliance with requirements in NSTS 1700.7B, Section 208. Injury to personnel and/or damage to STS equipment due to sharp edges, corners, protrusions, etc., are prevented by compliance with the requirements of NSTS 1700.7B, Section 217.

The incorporation of redundancy and inhibits in the AFIS design enhances the failure tolerance and safe operation of fluid couplings, fluid vent valves, fluid component heater circuits and the emergency demate mechanism. Explosion hazards are controlled by the separation and isolation of fluid components containing incompatible fluids, such as fuel and oxidizer. The requirements of NSTS 1700.7B, Sections 200-210, 213, and 219 apply to these AFIS components and associated hazards.

The ability to release the receiving spacecraft in the event of docking mechanism failure is insured by the use of EVA-releasable or EVA-operable docking components and non-latching fluid couplings in the AFIS design. The requirements of NSTS 1700.7B, Sections 200, 203-205, 216, and 217 are applicable.

### 4.7.3 Fluid Coupler/Electrical Connector Layout

The fluid coupler layout is designed to maximize safety by maximizing the distance between hazardous propellants and cryogenics. The MMH fluid coupler will be located on the opposite side of the AFIS from the  $N_2O_4$  fluid coupler and the LOX and  $LH_2$  fluid couplers are similarly separated. The connectors utilized for data are separated  $180^\circ$  from the electrical power connectors to minimize EMI/EMC problems. **Figure 4-30** shows the proposed fluid coupling arrangement.

It is envisioned that the propellants will be transferred in a serial fashion. The fluid trapped in the lines after propellant transfer will be vented to space, either directly to space or through a catalysis bed.

STS PAYLOAD SAFETY REQUIREMENTS APPLICABILITY MATRIX		1. PAYLOAD/SUBSYSTEM:	2. DATE:	3. PHASE:	4. PAGE ____ OF ____																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																										
AFIS	5. PAYLOAD ELEMENT	6. R1001007A	R1001007B	R1001007C	R1001007D	R1001007E	R1001007F	R1001007G	R1001007H	R1001007I	R1001007J	R1001007K	R1001007L	R1001007M	R1001007N	R1001007O	R1001007P	R1001007Q	R1001007R	R1001007S	R1001007T	R1001007U	R1001007V	R1001007W	R1001007X	R1001007Y	R1001007Z	R1001007AA	R1001007AB	R1001007AC	R1001007AD	R1001007AE	R1001007AF	R1001007AG	R1001007AH	R1001007AI	R1001007AJ	R1001007AK	R1001007AL	R1001007AM	R1001007AN	R1001007AO	R1001007AP	R1001007AQ	R1001007AR	R1001007AS	R1001007AT	R1001007AU	R1001007AV	R1001007AW	R1001007AX	R1001007AY	R1001007AZ	R1001007BA	R1001007BB	R1001007BC	R1001007BD	R1001007BE	R1001007BF	R1001007BG	R1001007BH	R1001007BI	R1001007BJ	R1001007BK	R1001007BL	R1001007BM	R1001007BN	R1001007BO	R1001007BP	R1001007BQ	R1001007BR	R1001007BS	R1001007BT	R1001007BU	R1001007BV	R1001007BW	R1001007BX	R1001007BY	R1001007BZ	R1001007CA	R1001007CB	R1001007CC	R1001007CD	R1001007CE	R1001007CF	R1001007CG	R1001007CH	R1001007CI	R1001007CJ	R1001007CK	R1001007CL	R1001007CM	R1001007CN	R1001007CO	R1001007CP	R1001007CQ	R1001007CR	R1001007CS	R1001007CT	R1001007CU	R1001007CV	R1001007CW	R1001007CX	R1001007CY	R1001007CZ	R1001007DA	R1001007DB	R1001007DC	R1001007DD	R1001007DE	R1001007DF	R1001007DG	R1001007DH	R1001007DI	R1001007DJ	R1001007DK	R1001007DL	R1001007DM	R1001007DN	R1001007DO	R1001007DP	R1001007DQ	R1001007DR	R1001007DS	R1001007DT	R1001007DU	R1001007DV	R1001007DW	R1001007DX	R1001007DY	R1001007DZ	R1001007EA	R1001007EB	R1001007EC	R1001007ED	R1001007EE	R1001007EF	R1001007EG	R1001007EH	R1001007EI	R1001007EJ	R1001007EK	R1001007EL	R1001007EM	R1001007EN	R1001007EO	R1001007EP	R1001007EQ	R1001007ER	R1001007ES	R1001007ET	R1001007EU	R1001007EV	R1001007EW	R1001007EX	R1001007EY	R1001007EZ	R1001007FA	R1001007FB	R1001007FC	R1001007FD	R1001007FE	R1001007FF	R1001007FG	R1001007FH	R1001007FI	R1001007FJ	R1001007FK	R1001007FL	R1001007FM	R1001007FN	R1001007FO	R1001007FP	R1001007FQ	R1001007FR	R1001007FS	R1001007FT	R1001007FU	R1001007FV	R1001007FW	R1001007FX	R1001007FY	R1001007FZ	R1001007GA	R1001007GB	R1001007GC	R1001007GD	R1001007GE	R1001007GF	R1001007GG	R1001007GH	R1001007GI	R1001007GJ	R1001007GK	R1001007GL	R1001007GM	R1001007GN	R1001007GO	R1001007GP	R1001007GQ	R1001007GR	R1001007GS	R1001007GT	R1001007GU	R1001007GV	R1001007GW	R1001007GX	R1001007GY	R1001007GZ	R1001007HA	R1001007HB	R1001007HC	R1001007HD	R1001007HE	R1001007HF	R1001007HG	R1001007HH	R1001007HI	R1001007HJ	R1001007HK	R1001007HL	R1001007HM	R1001007HN	R1001007HO	R1001007HP	R1001007HQ	R1001007HR	R1001007HS	R1001007HT	R1001007HU	R1001007HV	R1001007HW	R1001007HX	R1001007HY	R1001007HZ	R1001007IA	R1001007IB	R1001007IC	R1001007ID	R1001007IE	R1001007IF	R1001007IG	R1001007IH	R1001007II	R1001007IJ	R1001007IK	R1001007IL	R1001007IM	R1001007IN	R1001007IO	R1001007IP	R1001007IQ	R1001007IR	R1001007IS	R1001007IT	R1001007IU	R1001007IV	R1001007IW	R1001007IX	R1001007IY	R1001007IZ	R1001007JA	R1001007JB	R1001007JC	R1001007JD	R1001007JE	R1001007JF	R1001007JG	R1001007JH	R1001007JI	R1001007JJ	R1001007JK	R1001007JL	R1001007JM	R1001007JN	R1001007JO	R1001007JP	R1001007JQ	R1001007JR	R1001007JS	R1001007JT	R1001007JU	R1001007JV	R1001007JW	R1001007JX	R1001007JY	R1001007JZ	R1001007KA	R1001007KB	R1001007KC	R1001007KD	R1001007KE	R1001007KF	R1001007KG	R1001007KH	R1001007KI	R1001007KJ	R1001007KK	R1001007KL	R1001007KM	R1001007KN	R1001007KO	R1001007KP	R1001007KQ	R1001007KR	R1001007KS	R1001007KT	R1001007KU	R1001007KV	R1001007KW	R1001007KX	R1001007KY	R1001007KZ	R1001007LA	R1001007LB	R1001007LC	R1001007LD	R1001007LE	R1001007LF	R1001007LG	R1001007LH	R1001007LI	R1001007LJ	R1001007LK	R1001007LL	R1001007LM	R1001007LN	R1001007LO	R1001007LP	R1001007LQ	R1001007LR	R1001007LS	R1001007LT	R1001007LU	R1001007LV	R1001007LW	R1001007LX	R1001007LY	R1001007LZ	R1001007MA	R1001007MB	R1001007MC	R1001007MD	R1001007ME	R1001007MF	R1001007MG	R1001007MH	R1001007MI	R1001007MJ	R1001007MK	R1001007ML	R1001007MM	R1001007MN	R1001007MO	R1001007MP	R1001007MQ	R1001007MR	R1001007MS	R1001007MT	R1001007MU	R1001007MV	R1001007MW	R1001007MX	R1001007MY	R1001007MZ	R1001007NA	R1001007NB	R1001007NC	R1001007ND	R1001007NE	R1001007NF	R1001007NG	R1001007NH	R1001007NI	R1001007NJ	R1001007NK	R1001007NL	R1001007NM	R1001007NN	R1001007NO	R1001007NP	R1001007NQ	R1001007NR	R1001007NS	R1001007NT	R1001007NU	R1001007NV	R1001007NW	R1001007NX	R1001007NY	R1001007NZ	R1001007OA	R1001007OB	R1001007OC	R1001007OD	R1001007OE	R1001007OF	R1001007OG	R1001007OH	R1001007OI	R1001007OJ	R1001007OK	R1001007OL	R1001007OM	R1001007ON	R1001007OO	R1001007OP	R1001007OQ	R1001007OR	R1001007OS	R1001007OT	R1001007OU	R1001007OV	R1001007OW	R1001007OX	R1001007OY	R1001007OZ	R1001007PA	R1001007PB	R1001007PC	R1001007PD	R1001007PE	R1001007PF	R1001007PG	R1001007PH	R1001007PI	R1001007PJ	R1001007PK	R1001007PL	R1001007PM	R1001007PN	R1001007PO	R1001007PP	R1001007PQ	R1001007PR	R1001007PS	R1001007PT	R1001007PU	R1001007PV	R1001007PW	R1001007PX	R1001007PY	R1001007PZ	R1001007QA	R1001007QB	R1001007QC	R1001007QD	R1001007QE	R1001007QF	R1001007QG	R1001007QH	R1001007QI	R1001007QJ	R1001007QK	R1001007QL	R1001007QM	R1001007QN	R1001007QO	R1001007QP	R1001007QQ	R1001007QR	R1001007QS	R1001007QT	R1001007QU	R1001007QV	R1001007QW	R1001007QX	R1001007QY	R1001007QZ	R1001007RA	R1001007RB	R1001007RC	R1001007RD	R1001007RE	R1001007RF	R1001007RG	R1001007RH	R1001007RI	R1001007RJ	R1001007RK	R1001007RL	R1001007RM	R1001007RN	R1001007RO	R1001007RP	R1001007RQ	R1001007RR	R1001007RS	R1001007RT	R1001007RU	R1001007RV	R1001007RW	R1001007RX	R1001007RY	R1001007RZ	R1001007SA	R1001007SB	R1001007SC	R1001007SD	R1001007SE	R1001007SF	R1001007SG	R1001007SH	R1001007SI	R1001007SJ	R1001007SK	R1001007SL	R1001007SM	R1001007SN	R1001007SO	R1001007SP	R1001007SQ	R1001007SR	R1001007SS	R1001007ST	R1001007SU	R1001007SV	R1001007SW	R1001007SX	R1001007SY	R1001007SZ	R1001007TA	R1001007TB	R1001007TC	R1001007TD	R1001007TE	R1001007TF	R1001007TG	R1001007TH	R1001007TI	R1001007TJ	R1001007TK	R1001007TL	R1001007TM	R1001007TN	R1001007TO	R1001007TP	R1001007TQ	R1001007TR	R1001007TS	R1001007TT	R1001007TU	R1001007TV	R1001007TW	R1001007TX	R1001007TY	R1001007TZ	R1001007UA	R1001007UB	R1001007UC	R1001007UD	R1001007UE	R1001007UF	R1001007UG	R1001007UH	R1001007UI	R1001007UJ	R1001007UK	R1001007UL	R1001007UM	R1001007UN	R1001007UO	R1001007UP	R1001007UQ	R1001007UR	R1001007US	R1001007UT	R1001007UU	R1001007UV	R1001007UW	R1001007UX	R1001007UY	R1001007UZ	R1001007VA	R1001007VB	R1001007VC	R1001007VD	R1001007VE	R1001007VF	R1001007VG	R1001007VH	R1001007VI	R1001007VJ	R1001007VK	R1001007VL	R1001007VM	R1001007VN	R1001007VO	R1001007VP	R1001007VQ	R1001007VR	R1001007VS	R1001007VT	R1001007VU	R1001007VV	R1001007VW	R1001007VX	R1001007VY	R1001007VZ	R1001007WA	R1001007WB	R1001007WC	R1001007WD	R1001007WE	R1001007WF	R1001007WG	R1001007WH	R1001007WI	R1001007WJ	R1001007WK	R1001007WL	R1001007WM	R1001007WN	R1001007WO	R1001007WP	R1001007WQ	R1001007WR	R1001007WS	R1001007WT	R1001007WU	R1001007WV	R1001007WW	R1001007WX	R1001007WY	R1001007WZ	R1001007XA	R1001007XB	R1001007XC	R1001007XD	R1001007XE	R1001007XF	R1001007XG	R1001007XH	R1001007XI	R1001007XJ	R1001007XK	R1001007XL	R1001007XM	R1001007XN	R1001007XO	R1001007XP	R1001007XQ	R1001007XR	R1001007XS	R1001007XT	R1001007XU	R1001007XV	R1001007XW	R1001007XX	R1001007XY	R1001007XZ	R1001007YA	R1001007YB	R1001007YC	R1001007YD	R1001007YE	R1001007YF	R1001007YG	R1001007YH	R1001007YI	R1001007YJ	R1001007YK	R1001007YL	R1001007YM	R1001007YN	R1001007YO	R1001007YP	R1001007YQ	R1001007YR	R1001007YS	R1001007YT	R1001007YU	R1001007YV	R1001007YW	R1001007YX	R1001007YY	R1001007YZ	R1001007ZA	R1001007ZB	R1001007ZC	R1001007ZD	R1001007ZE	R1001007ZF	R1001007ZG	R1001007ZH	R1001007ZI	R1001007ZJ	R1001007ZK	R1001007ZL	R1001007ZM	R1001007ZN	R1001007ZO	R1001007ZP	R1001007ZQ	R1001007ZR	R1001007ZS	R1001007ZT	R1001007ZU	R1001007ZV	R1001007ZW	R1001007ZX	R1001007ZY	R1001007ZZ
		7. SAFETY ANALYSIS BY: (NAME, ORG, INITIAL)																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																													

Figure 4-28 STS Payload Safety Requirements Applicability Matrix

AFIS SYSTEM HAZARDS	CONTROLLED BY			
	INHIBITS	DESIGN	MFG/TEST	OPN
• LEAKAGE OR RUPTURE IN FLUID SUBSYSTEM DUE TO STRUCTURAL FAILURE		X	X	
• LEAKAGE OR RUPTURE IN FLUID SUBSYSTEM DUE TO FAILURE OF HEATER CIRCUIT	X	X	X	
• FAILURE OR INADVERTENT ACTUATION OF AFIS VENT VALVES	X	X	X	
• FAILURE OR IMPROPER MATING OF FLUID COUPLINGS		X	X	
• INABILITY TO RELEASE RECEIVING SPACECRAFT AFTER SERVICING		X		X
• INADVERTENT ACTUATION OF THE EMERGENCY DEMATE MECHANISM	X	X		
• INJURY OR DAMAGE RESULTING FROM SHARP EDGES, CORNERS, PROTRUSIONS, ETC.		X	X	
• IGNITION OF FLAMMABLE ATMOSPHERES	X	X		
• FAILURE OF PRIMARY STRUCTURE		X	X	
• EXPLOSION DUE TO FUEL AND OXIDIZER IN CLOSE PROXIMITY	X	X		X

Figure 4-29 AFIS Safety Assessment

ORIGINAL PAGE IS OF POOR QUALITY




Figure 4-30 Fluid Coupler and Electrical Connector Layout

## 5.0 DEMONSTRATION UNIT

### 5.1 DEMONSTRATION OBJECTIVE

An Engineering working model of AFIS was constructed to demonstrate the proof of concept. All of the AFIS subsystems with the exception of the pyros were operated in a scenario representing a typical fluid transfer mission. A detailed description of the procedures can be found in "Test Plan and Operational Procedures", Fairchild Space, April 1990, NAS8-37457. In order to demonstrate a typical fluid transfer operation, a satellite simulator was designed and constructed. The simulator provided the interface needed for mounting the fluid coupler. It also provided the structural frame for simulating the 2,000 lbs fluid transfer force.

A summary of the functions and tests performed is provided below:

- a) Raise and engage latches.
- b) Open contamination covers.
- c) Raise shelf assembly and engage fluid coupler.
- d) Transfer fluid through coupler.
- e) Apply 2,000# load to AFIS interface.
- f) Break interface with emergency de-mate.
- g) Raise shelf assembly again and re-mate coupler.
- h) Lower shelf assembly.
- i) Close contamination covers.
- j) Disengage latches.

The 0.25 inch over-travel and 0.1 inch lateral misalignment requirements were demonstrated by repeating the same procedure described above for the nominal condition.

### 5.2 DEMO MECHANICAL CONFIGURATION

The AFIS demonstration unit mechanical design is similar to the flight design. The major changes involve lubricants and motor

selection. The rationale for these changes was to reduce cost without sacrificing performance. Each of the major systems is listed below, along with the listed components that are not flight qualified.

#### 5.2.1 Cover Mechanism

This mechanism is essentially the same as the flight unit. The only changes from the flight design involve the motor selection and the design of the cover fans. For the flight design, a flight qualified motor would need to be used. The cover fans would be made of aluminum honeycomb to reduce weight. The microswitches that control the travel of the covers would need to be flight qualified parts. The cover backup release was not incorporated on the demonstration unit because of the pyro device that is required for the release.

#### 5.2.2 Latch Mechanism

The Latch Mechanism is essentially the same as the flight design, with only a few modifications. The motor would need to be a flight qualified unit, and the lubricants would need to be flight qualified. A carbon steel chain was used for the demo unit; a stainless steel chain would be used for flight. Additionally, carbon steel sprockets were used instead of stainless steel to reduce cost. The bearings that were used in the mechanism were not flight qualified since commercially available parts cost less. Non-flight qualified microswitches were used.

#### 5.2.3 Shelf Drive Mechanism

The shelf drive mechanism is similar to the corresponding flight design, with only a few exceptions. The emergency disconnect is manually operated rather than

operated by a solenoid. The chain drive components are commercially available carbon steel rather than stainless steel. No flight lubricants are used. Non-flight qualified microswitches were used.

#### 5.2.4 Structure

The demo AFIS structure is essentially the same as the flight AFIS structure. Honeycomb panels would be installed in the flight unit for the radial ribs and for the legs to reduce weight. Appendix D itemizes the demo AFIS weights.

### 5.3 DEMO ELECTRICAL SYSTEM

The AFIS demonstration unit electrical system simulates the flight unit electrical system by using a series of remotely actuated relays to drive the mechanisms. Tables 7 and 8 list the electrical interfaces and hardware considerations for the AFIS demo unit. The demo unit electrical system consists of the following three main elements: the remote controller, the remote relay chassis, and the sensors and motors mounted on the AFIS (see **Figure 5-1**)

The remote controller provides the control and 12 volt DC power necessary to control and drive the latch and cover mechanism motors. The coupler shelf drive, which is driven by an AC motor, is controlled remotely via 12 volt relays. The status of all mechanisms and their respective End of Travel (EOT) limits are provided by

indicators on the remote control panel, as shown in **Figure 5-2**. The method of operation to be used with this panel is as follows: the operation decides which system is to be driven, selects the direction of travel and then activates the drive switch for that particular function. The demo unit design concept lends itself well to the remote operation needed for eventual flight application. The remote controller would be replaced with either an STS or ground based command and telemetry system to conduct on-orbit operations.

The remote control relay chassis, that provides the relay activation and status sensing of the mechanisms, is located on the AFIS unit. The remote unit contains the necessary relays and sensing resistors to carry out the functions necessary to drive and stop the mechanisms. This unit simulates the actual Remote Interface Unit (RIU) functions that would be provided in a flight version of the AFIS.

The sensors and motors are mounted on the AFIS mechanical system as required to perform the electrical to mechanical interface. For purposes of the demonstration unit, the EOT sensors selected are microswitches, but for flight several other proximity sensing techniques will be considered. The motors are also standard 12 volt DC brushless DC motors or stepper motors as required for the flight application.

**Table 7. Demo Electrical Interfaces**

Power	Commands	Telemetry
Coupler Shelf Drive Motor	Latch Operation	Heater Thermistor Readout
Cover Mechanism Motor	Cover Mechanism Operation	Cover Status
Latch Motor	Coupler Shelf Mechanism	Coupler Shelf Status

**Table 8. Demo Electrical Hardware**

Name	Type
Coupler Shelf Drive Motor	110 V AC Motor & Gear Reducer
Cover Mechanism Drive Motor	12 V DC Motor & Gear Reducer
Latch Motor	TBD
Emergency Disconnect Solenoid	Manual Only
Heaters	None
Thermistors	None
AFIS Control Unit	GSE
Latch Motor	12V DC Motor & Gear Reducer

ORIGINAL PAGE IS  
OF POOR QUALITY




Figure 5-1 AFIS/Controller Interconnect Diagram




Figure 5-2 AFIS Remote Controller

## APPENDIX A WEIGHTS-FULLY LADEN (THREE TABLES)

Assembly Level	Assembly Components	Subassembly Components	Unit Wt Pounds	QTY	Quantity Weight Pounds	% Breakdown of Current Weight			Weight Plus Margin (total)	Comments	
						Est'd 20% margin	Cal'd 10% margin	Actual 5% margin			
MAIN STRUCTURE ASSEMBLY 7A1200	OUTER SKIN		9.580	1	9.580		100		10.538	-	
	INNER SKIN		5.770	1	5.770		100		6.347	-	
	MAIN DRIVE MOTORS		1.320	2	2.640	100			3.168	-	
	BASE RING ASSEMBLY		26.220	1	26.220		100		28.842	7A1201	
	RADIAL SUPPORT RIB		2.570	6	15.420		100		16.962	7A1202	
	UPPER RING, OUTER		10.470	1	10.470		100		11.517	7A1203	
	RING, INNER		6.840	1	6.840		100		7.524	7A1204	
	BALL SCREWS		2.000	18	36.000		100		39.6	7A1205	
	THRUST BEARINGS		0.130	18	2.340			100	2.457	AUBURN	
	DRIVE SPROCKETS		0.160	20	3.200			100	3.36	BROWNING	
	CHAIN		2.610	1	2.610		100		2.871	BERG	
	IDLER SPROCKETS		0.140	36	5.040			100	5.292	BROWNING	
	IDLER SHAFTS		0.055	36	1.980			100	2.079	BROWNING	
	BALL SCREW MNTG. BLOCK		0.097	18	1.746		100		1.9206	7A1201	
	STIFFENER ANGLE (INNER)		0.277	12	3.324		100		3.6564	7A1201	
	STIFFENER ANGLE (OUTER)		0.126	12	1.512		100		1.6632	7A1201	
	SUPPORT LEG		10.690	4	42.760		100		47.036	7A1201	
	<b>Subtotal</b>			<b>177.452</b>	<b>composite margin=</b>		<b>9.79%</b>	<b>194.83</b>			
FLUID SPACER ASSY. 7A1210	FRAME, BALL SCREW-FLUID		6.090	2	12.180		100		13.398	7A1211	
	SPACER ASSY.-FLUID		5.300	2	10.600		100		11.66	7A1212	
	<b>Subtotal</b>			<b>22.780</b>	<b>composite margin=</b>		<b>10.01%</b>	<b>25.06</b>			
GASELEC SPACER ASSY. 7A1220	FRAME, BALL SCREW-GASELEC		5.550	2	11.100		100		12.21	7A1221	
	SPACER ASSY.-GASELEC.		5.750	2	11.500		100		12.65	7A1222	
	<b>Subtotal</b>			<b>22.600</b>	<b>composite margin=</b>		<b>10.00%</b>	<b>24.86</b>			
CRYO SPACER ASSY. 7A1230	FRAME BALL SCREW-CRYO		6.940	2	13.880		100		15.268	7A1231	
	SPACER ASSY.-CRYO		1.950	4	7.800		100		8.58	7A1232	
	<b>Subtotal</b>			<b>21.680</b>	<b>composite margin=</b>		<b>10.01%</b>	<b>23.85</b>			
TENSIONER ASSEMBLY 7A1240	IDLER SPROCKET		0.120	7	0.840		100		0.924	BROWNING	
	IDLER SHAFT		0.055	7	0.385		100		0.4235	BROWNING	
	HOUSING		0.060	7	0.420		100		0.462	7A1241	
	GUIDE SHAFT		0.036	14	0.504		100		0.5544	7A1242	
	RETAINER		0.071	7	0.497		100		0.5467	7A1243	
	LEAD SCREW		0.010	3	0.030		100		0.033	7A1244	
	<b>Subtotal</b>			<b>2.676</b>	<b>composite margin=</b>		<b>9.87%</b>	<b>2.94</b>			
COVER MECHANISM ASSEMBLY 7A1300	RING, UPPER		1.190	1	1.190		100		1.309	7A1310	
	RING, LOWER		0.980	1	0.980		100		1.078	7A1311	
	LOWER FRAME 7A11312	RING, LOWER FRAME		2.960	1	2.960		100		3.256	-
		CHAIN		0.082	1	0.082		100		0.0902	BERG
		ROLLER		0.002	10	0.020		100		0.022	7A1304
		PIN		0.001	10	0.010		100		0.011	7A1305
		SHAFT		0.003	1	0.003		100		0.0033	7A1307
	UPPER FRAME 7A1313	RING, UPPER FRAME		3.020	1	3.020		100		3.322	-
		CHAIN		0.140	1	0.140		100		0.154	BERG
		ROLLER		0.092	8	0.016		100		0.0176	7A1304
		PIN		0.001	8	0.008		100		0.0088	7A1305
		WHEEL		0.002	3	0.006		100		0.0066	7A1306
	COVER FAN 7A1316	SHAFT		0.003	3	0.009		100		0.0099	7A1307
		RETAINER		0.002	3	0.006		100		0.0066	7A1308
		COVER		0.636	4	2.544		100		2.7984	7A1316
		SLIDE, UPPER		0.002	16	0.032		100		0.0352	7A1315
		SLIDE, LOWER		0.002	16	0.032		100		0.0352	7A1317
OUTER RING, LOWER COVER		4.320	1	4.320		100		4.752	7A1318		
OUTER RING, UPPER COVER		1.780	1	1.780		100		1.958	7A1319		
	<b>Subtotal</b>			<b>17.158</b>	<b>composite margin=</b>		<b>9.98%</b>	<b>18.87</b>			
COVER GEAR HOUSING ASSEMBLY 7A1301	HOUSING SUB-ASSEMBLY		0.230	1	0.230		100		0.253	7A1302	
	COVER		0.073	1	0.073		100		0.0803	7A1303	
	SHAFT, SPROCKET		0.008	1	0.008		100		0.0088	7A1309	
	COVER DRIVE MOTOR		1.320	1	1.320		100		1.452	7A1314	
	PLATE, ADAPTER GEAR		0.029	1	0.029		100		0.0319	7A1320	
	DRIVE GEAR ASSY		0.052	1	0.052		100		0.0572	7A1323	
	SPROCKET ASSY		0.129	1	0.129		100		0.1419	7A1324	
	SPROCKET ASSY-LG PITCH DIA		0.153	1	0.153		100		0.1683	7A1325	
	<b>Subtotal</b>			<b>1.994</b>	<b>composite margin=</b>		<b>9.83%</b>	<b>2.19</b>			

Assembly Level	Assembly Components	Subassembly Components	Unit Wt Pounds	QTY	Quantity Weight Pounds	% Breakdown of Current Weight			Weight Plus Margin (total)	Comments
						Esfd 20% margin	Cal'd 10% margin	Actual 5% margin		
DISCONNECT ASSEMBLY 7A1400	SHAFT		0.110	2	0.220		100		0.242	7A1401
	UPPER COUPLING		0.106	2	0.212		100		0.2332	7A1402
	LOWER COUPLING		0.185	2	0.370		100		0.407	7A1403
	PIN, YOKE		0.004	4	0.016		100		0.0176	7A1404
	YOKE		0.088	2	0.176		100		0.1936	7A1405
	YOKE PIVOT PIN		0.012	2	0.024		100		0.0264	7A1406
	MOTOR COUPLER		0.237	2	0.474		100		0.5214	7A1407
	MOTOR HOUSING		0.482	2	0.964		100		1.0604	7A1408
	HANDLE		0.431	2	0.862		100		0.9482	7A1409
	<b>Subtotal</b>				<b>3.318</b>	<b>composite margin=</b>	<b>10.01%</b>		<b>3.65</b>	
LATCH MECHANISM 7A1500	CHAIN		2.000	1	2.000		100		2.4	
	MOTOR		4.000	1	4.000		100		4.8	
	MISC. HARDWARE		10.000	1	10.000		100		12	
	<b>Subtotal</b>				<b>16.000</b>	<b>composite margin=</b>	<b>20.00%</b>		<b>19.20</b>	
THERMAL CONTROL HARDWARE	HEATERS		0.100	1	0.100		100		0.12	
	BLANKETS		10.000	1	10.000		100		12	
	ISOLATORS		5.000	1	5.000		100		6	
	SENSORS		2.000	1	2.000		100		2.4	
	<b>Subtotal</b>				<b>17.100</b>	<b>composite margin=</b>	<b>20.00%</b>		<b>20.52</b>	
ELECTRONICS AND WIRING HARNESS	CONTROL ELECTRONICS		20.000	1	20.000		100		24	
	REMOTE UNIT		10.800	1	10.800		100		12.96	
	ELECTRICAL HARNESS		10.000	1	10.000		100		12	
	<b>Subtotal</b>				<b>40.800</b>	<b>composite margin=</b>	<b>20.00%</b>		<b>48.96</b>	
<b>AFIS SUBTOTAL</b>					<b>343.558</b>	<b>composite margin=</b>	<b>12.04%</b>		<b>384.930</b>	
GFE COUPLERS AND CONNECTORS	Cryogen Coupler		4.000	4	16.000		100		19	
	Gas Coupler		2.500	4	10.000		100		12	
	Liquid Coupler		2.000	8	16.000		100		19	
	Electrical Connector		3.000	8	24.000		100		29	
	<b>Subtotal</b>				<b>66.000</b>	<b>composite margin=</b>	<b>19.70%</b>		<b>79</b>	
<b>AFIS TOTAL</b>					<b>409.558</b>	<b>composite margin=</b>	<b>13.28%</b>		<b>463.93</b>	

## APPENDIX B WEIGHTS-CRYOGEN CONFIGURATION (TWO TABLES)

Assembly Level	Assembly Components	Subassembly Components	Unit Wt Pounds	QTY	Quantity Weight Pounds	% Breakdown of Current Weight			Weight Plus Margln (total)	Comments	
						Est'd 20% margin	Ca'd 10% margin	Actual 5% margin			
MAIN STRUCTURE ASSEMBLY 7A1200	OUTER SKIN		9.580	1	9.580		100		10.538	-	
	INNER SKIN		5.770	1	5.770		100		6.347	-	
	MAIN DRIVE MOTORS		1.320	2	2.640	100			3.168	-	
	BASE RING ASSEMBLY		26.220	1	26.220		100		28.842	7A1201	
	RADIAL SUPPORT RIB		2.570	6	15.420		100		16.962	7A1202	
	UPPER RING, OUTER		10.470	1	10.470		100		11.517	7A1203	
	RING, INNER		6.840	1	6.840		100		7.524	7A1204	
	BALL SCREWS		2.000	12	24.000		100		26.4	7A1205	
	THRUST BEARINGS		0.130	12	1.560			100	1.638	AUBURN	
	DRIVE SPROCKETS		0.160	14	2.240			100	2.352	BROWNING	
	CHAIN		1.740	1	1.740		100		1.914	BERG	
	IDLER SPROCKETS		0.140	24	3.360			100	3.528	BROWNING	
	IDLER SHAFTS		0.055	24	1.320			100	1.386	BROWNING	
	BALL SCREW MNTG. BLOCK		0.097	12	1.164		100		1.2804	7A1201	
	STIFFENER ANGLE (INNER)		0.277	12	3.324		100		3.6564	7A1201	
	STIFFENER ANGLE (OUTER)		0.126	12	1.512		100		1.6632	7A1201	
SUPPORT LEG		10.690	4	42.760		100		47.036	7A1201		
<b>Subtotal</b>				<b>159.920</b>	<b>composite</b>	<b>margin=</b>	<b>9.90%</b>	<b>175.75</b>			
CRYO SPACER ASSY. 7A1230	FRAME, BALL SCREW-CRYO		6.940	2	13.880		100		15.268	7A1211	
	SPACER ASSY.-CRYO		1.950	4	7.800		100		8.58	7A1212	
<b>Subtotal</b>				<b>21.680</b>	<b>composite</b>	<b>margin=</b>	<b>10.00%</b>	<b>23.85</b>			
GAS/ELEC SPACER ASSY. 7A1220	FRAME, BALL SCREW-GAS/ELEC		5.550	2	11.100		100		12.21	7A1221	
	SPACER ASSY.-GAS/ELEC.		5.750	2	11.500		100		12.65	7A1222	
<b>Subtotal</b>				<b>22.600</b>	<b>composite</b>	<b>margin=</b>	<b>10.00%</b>	<b>24.86</b>			
TENSIONER ASSEMBLY 7A1240	IDLER SPROCKET		0.120	7	0.840		100		0.924	BROWNING	
	IDLER SHAFT		0.055	7	0.385		100		0.4235	BROWNING	
	HOUSING		0.060	7	0.420		100		0.462	7A1241	
	GUIDE SHAFT		0.036	14	0.504		100		0.5544	7A1242	
	RETAINER		0.071	7	0.497		100		0.5467	7A1243	
	LEAD SCREW		0.010	3	0.030		100		0.033	7A1244	
<b>Subtotal</b>				<b>2.676</b>	<b>composite</b>	<b>margin=</b>	<b>10.00%</b>	<b>2.94</b>			
COVER MECHANISM ASSEMBLY 7A1300	RING, UPPER		1.190	1	1.190		100		1.309	7A1310	
	RING, LOWER		0.980	1	0.980		100		1.078	7A1311	
	LOWER FRAME 7A11312	RING, LOWER FRAME		2.960	1	2.960		100		3.256	-
		CHAIN		0.082	1	0.082		100		0.0902	BERG
		ROLLER		0.002	10	0.020		100		0.022	7A1304
		PIN		0.001	10	0.010		100		0.011	7A1305
		SHAFT		0.003	1	0.003		100		0.0033	7A1307
	UPPER FRAME 7A1313	RING, UPPER FRAME		3.020	1	3.020		100		3.322	-
		CHAIN		0.140	1	0.140		100		0.154	BERG
		ROLLER		0.002	8	0.016		100		0.0176	7A1304
		PIN		0.001	8	0.008		100		0.0088	7A1305
		WHEEL		0.002	3	0.006		100		0.0066	7A1306
	COVER FAN 7A1316	SHAFT		0.003	3	0.009		100		0.0099	7A1307
		RETAINER		0.002	3	0.006		100		0.0066	7A1308
		COVER		0.636	4	2.544		100		2.7984	7A1316
		SLIDE, UPPER		0.002	16	0.032		100		0.0352	7A1315
SLIDE, LOWER		0.002	16	0.032		100		0.0352	7A1317		
OUTER RING, LOWER COVER		4.320	1	4.320		100		4.752	7A1318		
OUTER RING, UPPER COVER		1.780	1	1.780		100		1.958	7A1319		
<b>Subtotal</b>				<b>17.158</b>	<b>composite</b>	<b>margin=</b>	<b>10.00%</b>	<b>18.87</b>			
COVER GEAR HOUSING ASSEMBLY 7A1301	HOUSING SUB-ASSEMBLY		0.230	1	0.230		100		0.253	7A1302	
	COVER		0.073	1	0.073		100		0.0803	7A1303	
	SHAFT, SPROCKET		0.008	1	0.008		100		0.0088	7A1309	
	COVER DRIVE MOTOR		1.320	1	1.320		100		1.452	7A1314	
	PLATE, ADAPTER GEAR		0.029	1	0.029		100		0.0319	7A1320	
	DRIVE GEAR ASSY		0.052	1	0.052		100		0.0572	7A1323	
	SPROCKET ASSY		0.129	1	0.129		100		0.1419	7A1324	
	SPROCKET ASSY-LG PITCH DIA		0.153	1	0.153		100		0.1683	7A1325	
<b>Subtotal</b>				<b>1.994</b>	<b>composite</b>	<b>margin=</b>	<b>10.00%</b>	<b>2.19</b>			
DISCONNECT ASSEMBLY 7A1400	SHAFT		0.110	2	0.220		100		0.242	7A1401	
	UPPER COUPLING		0.106	2	0.212		100		0.2332	7A1402	
	LOWER COUPLING		0.185	2	0.370		100		0.407	7A1403	
	PIN, YOKE		0.004	4	0.016		100		0.0176	7A1404	
	YOKE		0.088	2	0.176		100		0.1936	7A1405	
	YOKE PIVOT PIN		0.012	2	0.024		100		0.0264	7A1406	
	MOTOR COUPLER		0.237	2	0.474		100		0.5214	7A1407	
	MOTOR HOUSING		0.482	2	0.964		100		1.0604	7A1408	
	HANDLE		0.431	2	0.862		100		0.9482	7A1409	
<b>Subtotal</b>				<b>3.318</b>	<b>composite</b>	<b>margin=</b>	<b>10.00%</b>	<b>3.65</b>			

Assembly Level	Assembly Components	Subassembly Components	Unit Wt Pounds	QTY	Quantity Weight Pounds	% Breakdown of Current Weight			Weight Plus Margin (total)	Comments
						Estd 20% margin	Cal'd 10% margin	Actual 5% margin		
LATCH MECHANISM 7A1500	CHAIN		2.000	1	2.000	100			2.4	
	MOTOR		4.000	1	4.000	100			4.8	
	MISC. HARDWARE		10.000	1	10.000	100			12	
	<i>Subtotal</i>				<i>16.000</i>	<i>composite margin=</i>		<i>20.00%</i>	<i>19.20</i>	
THERMAL CONTROL HARDWARE	HEATERS		0.100	1	0.100	100			0.12	
	BLANKETS		10.000	1	10.000	100			12	
	ISOLATORS		5.000	1	5.000	100			6	
	SENSORS		2.000	1	2.000	100			2.4	
<i>Subtotal</i>				<i>17.100</i>	<i>composite margin=</i>		<i>20.00%</i>	<i>20.52</i>		
ELECTRONICS AND WIRING HARNESS	CONTROL ELECTRONICS		20.000	1	20.000	100			24	
	REMOTE UNIT		10.800	1	10.800	100			12.96	
	ELECTRICAL HARNESS		10.000	1	10.000	100			12	
	<i>Subtotal</i>				<i>40.800</i>	<i>composite margin=</i>		<i>20.00%</i>	<i>48.96</i>	
<b>AFIS SUBTOTAL</b>				<b>303.246</b>	<b>composite margin=</b>		<b>12.38%</b>	<b>340.801</b>		
GPE COUPLERS AND CONNECTORS	Cryogen Coupler		4.000	4	16.000	100			19	
	Gas Coupler		2.500	4	10.000	100			12	
	Liquid Coupler		0.000	0	0.000	100			0	
	Electrical Connector		3.000	8	24.000	100			29	
	<i>Subtotal</i>				<i>50.000</i>	<i>composite margin=</i>		<i>20.00%</i>	<i>60</i>	
<b>AFIS TOTAL</b>				<b>353.246</b>	<b>composite margin=</b>		<b>13.46%</b>	<b>400.801</b>		

## APPENDIX C WEIGHTS-FLUID CONFIGURATION (TWO TABLES)

Assembly Level	Assembly Components	Subassembly Components	Unit Wt Pounds	QTY	Quantity Weight Pounds	% Breakdown of Current Weight			Weight Plus Margin (total)	Comments	
						Est'd 20% margin	Cal'd 10% margin	Actual 5% margin			
MAIN STRUCTURE ASSEMBLY 7A1200	OUTER SKIN		9.580	1	9.580		100		10.538	-	
	INNER SKIN		5.770	1	5.770		100		6.347	-	
	MAIN DRIVE MOTORS		1.320	2	2.640	100			3.168	-	
	BASE RING ASSEMBLY		26.220	1	26.220		100		28.842	7A1201	
	RADIAL SUPPORT RIB		2.570	6	15.420		100		16.962	7A1202	
	UPPER RING, OUTER		10.470	1	10.470		100		11.517	7A1203	
	RING, INNER		6.840	1	6.840		100		7.524	7A1204	
	BALL SCREWS		2.000	12	24.000		100		26.4	7A1205	
	THRUST BEARINGS		0.130	12	1.560			100	1.638	AUBURN	
	DRIVE SPROCKETS		0.160	14	2.240			100	2.352	BROWNING	
	CHAIN		1.740	1	1.740			100	1.914	BERG	
	IDLER SPROCKETS		0.140	24	3.360			100	3.528	BROWNING	
	IDLER SHAFTS		0.055	24	1.320			100	1.386	BROWNING	
	BALL SCREW MNTG. BLOCK		0.097	12	1.164			100	1.2804	7A1201	
	STIFFENER ANGLE (INNER)		0.277	12	3.324			100	3.6564	7A1201	
	STIFFENER ANGLE (OUTER)		0.126	12	1.512			100	1.6632	7A1201	
SUPPORT LEG		10.690	4	42.760			100	47.036	7A1201		
<b>Subtotal</b>					<b>159.920</b>	<b>composite margin= 9.90%</b>		<b>175.75</b>			
FLUID SPACER ASSY. 7A1210	FRAME, BALL SCREW-FLUID		6.090	2	12.180		100		13.398	7A1211	
	SPACER ASSY.-FLUID		5.300	2	10.600		100		11.66	7A1212	
	<b>Subtotal</b>					<b>22.780</b>	<b>composite margin= 10.01%</b>		<b>25.06</b>		
GAS/ELEC SPACER ASSY. 7A1220	FRAME, BALL SCREW-GAS/ELEC		5.550	2	11.100		100		12.21	7A1221	
	SPACER ASSY.-GAS/ELEC.		5.750	2	11.500		100		12.65	7A1222	
	<b>Subtotal</b>					<b>22.600</b>	<b>composite margin= 10.00%</b>		<b>24.86</b>		
TENSIONER ASSEMBLY 7A1240	IDLER SPROCKET		0.120	7	0.840		100		0.924	BROWNING	
	IDLER SHAFT		0.055	7	0.385		100		0.4235	BROWNING	
	HOUSING		0.060	7	0.420		100		0.462	7A1241	
	GUIDE SHAFT		0.036	14	0.504		100		0.5544	7A1242	
	RETAINER		0.071	7	0.497		100		0.5467	7A1243	
	LEAD SCREW		0.010	3	0.030		100		0.033	7A1244	
<b>Subtotal</b>					<b>2.676</b>	<b>composite margin= 9.87%</b>		<b>2.94</b>			
COVER MECHANISM ASSEMBLY 7A1300	RING, UPPER		1.190	1	1.190		100		1.309	7A1310	
	RING, LOWER		0.980	1	0.980		100		1.078	7A1311	
	LOWER FRAME 7A11312	RING, LOWER FRAME		2.960	1	2.960		100		3.256	-
		CHAIN		0.082	1	0.082		100		0.0902	BERG
		ROLLER		0.002	10	0.020		100		0.022	7A1304
		PIN		0.001	10	0.010		100		0.011	7A1305
		SHAFT		0.003	1	0.003		100		0.0033	7A1307
	UPPER FRAME 7A1313	RING, UPPER FRAME		3.020	1	3.020		100		3.322	-
		CHAIN		0.140	1	0.140		100		0.154	BERG
		ROLLER		0.002	8	0.016		100		0.0176	7A1304
		PIN		0.001	8	0.008		100		0.0088	7A1305
		WHEEL		0.002	3	0.006		100		0.0066	7A1306
	COVER FAN 7A1316	SHAFT		0.003	3	0.009		100		0.0099	7A1307
		RETAINER		0.002	3	0.006		100		0.0066	7A1308
		COVER		0.636	4	2.544		100		2.7984	7A1316
		SLIDE, UPPER		0.002	16	0.032		100		0.0352	7A1315
SLIDE, LOWER		0.002	16	0.032		100		0.0352	7A1317		
OUTER RING, LOWER COVER		4.320	1	4.320		100		4.752	7A1318		
OUTER RING, UPPER COVER		1.780	1	1.780		100		1.958	7A1319		
<b>Subtotal</b>					<b>17.158</b>	<b>composite margin= 9.98%</b>		<b>18.87</b>			
COVER GEAR HOUSING ASSEMBLY 7A1301	HOUSING SUB-ASSEMBLY		0.230	1	0.230		100		0.253	7A1302	
	COVER		0.073	1	0.073		100		0.0803	7A1303	
	SHAFT, SPROCKET		0.008	1	0.008		100		0.0088	7A1309	
	COVER DRIVE MOTOR		1.320	1	1.320		100		1.452	7A1314	
	PLATE, ADAPTER GEAR		0.029	1	0.029		100		0.0319	7A1320	
	DRIVE GEAR ASSY		0.052	1	0.052		100		0.0572	7A1323	
	SPROCKET ASSY		0.129	1	0.129		100		0.1419	7A1324	
	SPROCKET ASSY-LG PITCH DIA		0.153	1	0.153		100		0.1683	7A1325	
<b>Subtotal</b>					<b>1.994</b>	<b>composite margin= 9.83%</b>		<b>2.19</b>			
DISCONNECT ASSEMBLY 7A1400	SHAFT		0.110	2	0.220		100		0.242	7A1401	
	UPPER COUPLING		0.106	2	0.212		100		0.2332	7A1402	
	LOWER COUPLING		0.185	2	0.370		100		0.407	7A1403	
	PIN, YOKE		0.004	4	0.016		100		0.0176	7A1404	
	YOKE		0.088	2	0.176		100		0.1936	7A1405	
	YOKE PIVOT PIN		0.012	2	0.024		100		0.0264	7A1406	
	MOTOR COUPLER		0.237	2	0.474		100		0.5214	7A1407	
	MOTOR HOUSING		0.482	2	0.964		100		1.0604	7A1408	
	HANDLE		0.431	2	0.862		100		0.9482	7A1409	
<b>Subtotal</b>					<b>3.318</b>	<b>composite margin= 10.01%</b>		<b>3.65</b>			

Assembly Level	Assembly Components	Subassembly Components	Unit Wt Pounds	QTY	Quantity Weight Pounds	% Breakdown of Current Weight			Weight Plus Margin (total)	Comments
						Est'd 20% margin	Cal'd 10% margin	Actual 5% margin		
LATCH MECHANISM 7A1500	CHAIN		2.000	1	2.000	100			2.4	
	MOTOR		4.000	1	4.000	100			4.8	
	MISC. HARDWARE		10.000	1	10.000	100			12	
	<i>Subtotal</i>				<i>16.000</i>	<i>composite margin=</i>		<i>20.00%</i>	<i>19.20</i>	
THERMAL CONTROL HARDWARE	HEATERS		0.100	1	0.100	100			0.12	
	BLANKETS		10.000	1	10.000	100			12	
	ISOLATORS		5.000	1	5.000	100			6	
	SENSORS		2.000	1	2.000	100			2.4	
<i>Subtotal</i>				<i>17.100</i>	<i>composite margin=</i>		<i>20.00%</i>	<i>20.52</i>		
ELECTRONICS AND WIRING HARNESS	CONTROL ELECTRONICS		20.000	1	20.000	100			24	
	REMOTE UNIT		10.800	1	10.800	100			12.96	
	ELECTRICAL HARNESS		10.000	1	10.000	100			12	
<i>Subtotal</i>				<i>40.800</i>	<i>composite margin=</i>		<i>20.00%</i>	<i>48.96</i>		
AFIS SUBTOTAL					304.346	<i>composite margin=</i>		<i>12.37%</i>	342.000	
GFE COUPLERS AND CONNECTORS	Cryogen Coupler		0.000	0	0.000	100			0	
	Gas Coupler		2.500	4	10.000	100			12	
	Liquid Coupler		2.000	8	16.000	100			19	
	Electrical Connector		3.000	8	24.000	100			29	
<i>Subtotal</i>				<i>50.000</i>	<i>composite margin=</i>		<i>20.00%</i>	<i>60</i>		
AFIS TOTAL					354.346	<i>composite margin=</i>		<i>13.45%</i>	402	

## APPENDIX D DEMO WEIGHTS

Assembly Components	Subassembly Components	Unit Weight Pounds	QTY	Current Item Weight Pounds (Total)	% Breakdown of Current Weight			Drawing Number
					Est'd.	Cal'd.	Act.	
MAIN STRUCTURE ASSEMBLY 7A1200	OUTER SKIN	12.770	1	12.770	0	100	0	-
	INNER SKIN	7.690	1	7.690	0	100	0	-
	MAIN DRIVE MOTORS AND DISCONNECT	17.140	2	34.280	0	0	100	7A1401
	BASE RING ASSEMBLY	67.500	1	67.500	0	0	100	7A1201
	RADIAL SUPPORT RIB ASSEMBLY	4.342	6	26.052	0	0	100	7A1209
	UPPER RING, OUTER	18.000	1	18.000	0	0	100	7A1203
	RING, INNER	11.300	1	11.300	0	0	100	7A1204
	BALL SCREWS	2.038	18	36.684	0	0	100	7A1205
	THRUST BEARINGS	0.122	18	2.196	0	0	100	T-100
	DRIVE SPROCKETS (MODIFIED)	0.338	20	6.760	0	0	100	7A1251
	CHAIN	2.610	1	2.610	0	100	0	
	BALL SCREW MNTG. BLOCK	0.087	18	1.566	0	0	100	7A1206
	SUPPORT LEG	15.400	4	61.600	0	100	0	7A1250
	MANUAL TENSIONER	0.230	2	0.460	0	0	100	7A1241
	SPRING TENSIONER	0.240	2	0.480	0	0	100	7A1242
<b>STRUCTURE SUBTOTAL</b>				<b>289.948</b>				
FLUID SPACER ASSY. 7A1210	FRAME, BALL SCREW - FLUID	7.900	2	15.800	0	0	100	7A1211
	SPACER ASSY. - FLUID	6.300	2	12.600	0	0	100	7A1212
	<b>SUBTOTAL</b>			<b>28.400</b>				
GAS/ELEC SPACER ASSY. 7A1220	FRAME, BALL SCREW - GAS/ELEC	7.300	2	14.600	0	0	100	7A1221
	SPACER ASSY. - GAS/ELEC.	7.160	2	14.320	0	0	100	7A1222
	<b>SUBTOTAL</b>			<b>28.920</b>				
CRYO SPACER ASSY. 7A1230	FRAME, BALL SCREW - CRYO	8.800	2	17.600	0	0	100	7A1231
	SPACER ASSY. - CRYO	1.900	0	0.000	0	0	100	7A1232
	<b>SUBTOTAL</b>			<b>17.600</b>				
COVER MECHANISM ASSEMBLY	RING, UPPER	2.310	1	2.310	0	100	0	7A1310
	RING, LOWER	1.900	1	1.900	0	100	0	7A1311
	LOWER RING FRAME ASSY	3.050	1	3.050	0	0	100	7A1312
	UPPER RING FRAME ASSY	3.100	1	3.100	0	0	100	7A1313
	COVER FAN	1.910	4	7.640	0	0	100	7A1316
	OUTER RING, LOWER COVER	3.150	1	3.150	0	0	100	7A1318
	OUTER RING, UPPER COVER	1.780	1	1.780	0	100	0	7A1319
	COVER GEAR HOUSING ASSEMBLY	1.760	1	1.760	0	0	100	7A1301
<b>COVER MECHANISM SUBTOTAL</b>				<b>24.690</b>				
LATCH ASSEMBLY WITH MOTOR		8.140	1	8.140	0	0	100	7A1500
LATCH ASSEMBLY WITHOUT MOTOR		7.110	2	14.220	0	0	100	7A1510
LATCH TENSIONER ASSEMBLY		2.000	3	6.000	100	0	0	7A1520
<b>AFIS SYSTEM TOTAL</b>				<b>417.918</b>				

